



Eco Process Assistance

De Prijkels • Venecoweg 19 • B-9810 Nazareth
 Tel. +32 9 381.51.30
 Fax +32 9 221.82.18
 www.epas.be • epas@epas.be

**MELISSA
 ENGINEERING OF THE WASTE
 COMPARTMENT**

ESA contract 15689/01/NL/ND

TECHNICAL NOTE 71.9.1

Test-Plan and Procedure

Version : 1
 Issue : 1

	Name	Signature
Prepared by:	Noëlle Michel	
Approved by:	Dries Demey	

17/06/2004



DOCUMENT CHANGE LOG

Version	Issue	Date	Observation
1	0	22/01/2004	Draft
1	1	17/06/2004	Final

DISTRIBUTION LIST

Quantity	Company/Department	Name
Quantity	Company/Department	Name
2	ESA	C. Lasseur
1	EPAS	D. Demey
		N. Michel
1	UAB	J.Albiol
		F. Godia
1	UBP	C.G. Dussap
		L. Poughon
1	SHERPA	J. Brunet
1	VITO	H. De wever
1	LabMET	W. Verstraete
1	U. Guelph	M.A. Dixon
1	SCK	M. Mergeay

CONTENT

1.	<u>INTRODUCTION</u>	6
1.1	OBJECTIVES	6
1.2	ARCHITECTURE OF THE FUNCTIONAL TEST PROCEDURE	6
2.	<u>REQUIREMENTS SPECIFICATIONS</u>	7
2.1	GENERAL DESCRIPTION	7
2.1.1	Hardware phase	7
2.1.2	Operation phase	7
2.2	PROTOTYPE INSTRUMENTATION	8
2.2.1	Reactor	9
2.2.2	Filtration unit	10
2.2.3	Gas loop	11
2.3	DETAILED SYSTEM REQUIREMENTS AND TESTS PRINCIPLES	12
3.	<u>TESTS NOMENCLATURE AND PROCEDURES</u>	15
3.1	NOMENCLATURE	15
3.2	TESTS PROCEDURES	15
3.2.1	Hardware phase	15
3.2.2	Operation phase	17
4.	<u>CONCLUSIONS</u>	24
5.	<u>REFERENCES</u>	24
6.	<u>ADDENDUM</u>	25
6.1	TEST PLAN: CLASSIFICATION BY INSTRUMENT	25
6.2	TEST PLAN: CLASSIFICATION BY NUMBER	29

LIST OF FIGURES

Figure 1. Instrumentation of the reactor	9
Figure 2. Instrumentation of the filtration unit.....	10
Figure 3. Instrumentation of the gas loop	11
Figure 4. Test plan nomenclature.....	15

LIST OF TABLES

Table 1. Requirements of the compartment for hardware phase	7
Table 2. Requirements of the compartment for operation phase	7
Table 3. Listing of requirements	12
Table 4. Analysis frequency	19
Table 5. Tests classification	29

1. Introduction

1.1 Objectives

The liquefying compartment of the MELiSSA loop is responsible for the biodegradation of human faecal material and other wastes (inedible parts of plant material) generated by the crew. The volatile fatty acids and ammonia produced during the anaerobic fermentation process are fed to the second photoheterotrophic compartment inoculated with the bacterium *Rhodospirillum rubrum*. The produced CO₂ is supplied to the photoautotrophic compartment inoculated with the algal strain *Arthrospira platensis* and to the higher plants compartment.


At the pilot plant of the University of Barcelona, the three compartments of the MELiSSA loop (photoheterotrophic compartment CIV, nitrifying compartment CIVI and photoautotrophic compartment CIVa) are already connected at lab scale and will be validated at pilot scale. In order to validate the whole MELiSSA loop, it is necessary to construct the first compartment at pilot scale (fermentation reactor) for the primary degradation of the waste produced by the crew.

However, between lab and pilot scales the construction of an intermediate prototype reactor represents an important step to evaluate and improve the theoretical concepts.

Once the prototype Waste Compartment is assembled, it is necessary to perform functional tests to evaluate the hardware and the process. A first series is performed to test individually the sensors, actuators and other instruments and equipment. After these functional tests the reactor is filled with the Melissa inoculum and fed with representative substrate. The next series of tests are performed for a period of one month, corresponding with three retention times (required for a representative process evaluation).

This technical note includes listing of requirements of the prototype and the related necessary tests. Organization of the tests and their principles and procedures are also described.

1.2 Architecture of the functional test procedure



The procedure followed to test the prototype consists first in a requirements analysis that highlights the critical points of the system to be tested. Based on this analysis, a test plan is written, organizing the tests.

Performance and evaluation of the tests can be found in the MELiSSA technical notes 71.9.3 and 71.9.4.

For a clearer structure of the work, the test plan is divided into two major levels: the hardware phase and the operation phase. The hardware phase concerns all the tests related to the instrumentation at start-up of the prototype. The operation phase consists in testing the process in a long-term running.

2. Requirements specifications

2.1 General description

The prototype reactor is aimed to perform an anaerobic digestion of a mixture composed of faecal material, toilet paper and plants, with the highest efficiency. This corresponds to the highest production of VFA and ammonium in the liquid phase, and CO₂ in the gas phase. To fill this general objective, the prototype must satisfy a certain number of criteria. These criteria vary from one phase to the other. The major part of these criteria is very specific of one type instrument. In the operation phase, more general requirements can be listed, concerning global evaluation of complete subsystems.

2.1.1 Hardware phase

Table 1 presents the main requirements of the hardware phase with the instrumentation concerned.

Table 1. Requirements of the compartment for hardware phase

Requirements	Related instrumentation
Liquid and gas tightness of the reactor	R-001, connections
Liquid tightness of the FU	FU, connections
Gas tightness of the Gas loop	Gas loop, connections
Accurate and repeatable measurements	Sensors, transmitters, PC interface
Sufficient and homogeneous mixing	Mixer
Sufficient and homogeneous heating	Heating element, warm water bath

2.1.2 Operation phase

Table 2 presents the main requirements of the operation phase with the instrumentation concerned. In this phase, the test plan includes the parallel evaluation of hardware and process during running of the prototype.

Table 2. Requirements of the compartment for operation phase

Requirements	Related instrumentation
For Hardware evaluation	
Absence of clogging of components	Membrane, pumps, connections, valves
Absence of corrosion / fouling of components	Reactors, pumps, valves and connections, sensors and actuators in contact with MELiSSA inoculum or

	biogas
Measurements continuously accurate and repeatable	Sensors, transmitters, interface
Absence of deterioration of tanks and instruments	Tanks, instruments
Correct answer of control	Controlled actuators
Correct regulation of permeate production	Filtration Unit
Correct pressure, flow and condensation regulation in gas phase	Gas Loop
Correct configurations of the sub-systems	Reactor, Filtration Unit, Gas Loop
<i>For Process evaluation (Biological requirements)</i>	
Optimisation of the filtration process	Filtration Unit
Optimisation of the VFA (Volatile Fatty Acids) production	Whole system
Optimisation of the NH ₄ ⁺ production	Whole system
Optimisation of the CO ₂ production	Whole system
Optimisation of the OM (Organic matter) degradation efficiency	Whole system
Optimisation of the Nitrogen degradation efficiency	Whole system
Optimisation of the Fibres degradation efficiency	Whole system

2.2 Prototype instrumentation

The next schemes present the hardware specific of the prototype reactor and its sub-systems (see Figure 1, Figure 2 and Figure 3). Instrumentation in gray is not present yet on the reactor.

CONFIDENTIAL REPORT
2.2.1 Reactor

Figure 1 presents instrumentation scheme of the reactor.





Figure 1. Instrumentation of the reactor

CONFIDENTIAL REPORT
2.2.2 Filtration unit

Figure 2 presents instrumentation scheme of the filtration unit.

Figure 2. Instrumentation of the filtration unit



2.2.3 Gas loop

Figure 3 presents instrumentation scheme of the gas loop.




Figure 3. Instrumentation of the gas loop

2.3 Detailed system requirements and tests principles

Based on the general system requirements, a detailed list of criteria that must be satisfied by the system is established, with the general related instrumentation.

For each phase the system requirements are listed together with the related instrumentation and the basis of the associated tests (see Table 3).

Table 3. Listing of requirements

Nber	Requirements	Related instrumentation										Test principle
		Reactor, tanks	Membrane	Pumps	Mixer	Heat exchanger	Balance	Valves and connections	Sensors, transmitters	Controller		
Hardware phase												
1	Homogeneous mixing											Check visually + analyse and compare composition of samples from bottom and top of reactor on representative period
2	Stable heating of the reactor (55°C)											Control on representative period the stability and accuracy of temperature
3	Gas tightness											Put reactor/system under pressure and measure on representative period the pressure stability (big leaks) or check small leaks with gas detector
4	Liquid tightness											Check visually absence of leakage
5	Running of sensors and actuators											Check visually running on/ off line
Operation phase												
Hardware evaluation												
1	Absence of clogging											Check regularly right flow and absence of clogging through piping
2	Absence of corrosion / fouling											Regular visual check

CONFIDENTIAL REPORT

3	Accuracy and repeatability of measurements																			Regular calibration
4	Absence of instrument deterioration																			Regular visual check
5	Absence of reactor deterioration																			Regular visual check
6	Desired answer to user or controller action																			Check right answer of instrument to one user/controller action
7	Regulation of permeate production																			Evaluate permeate production depending on selected program of the filtration unit
2	Regulation of gas loop																			Check correct regulation of the gas loop on a representative period
9	Configuration of reactor																			Evaluate general configuration of reactor
10	Configuration of filtration unit																			Evaluate general configuration of filtration unit
11	Configuration of gas loop																			Evaluate general configuration of gas loop
Process evaluation																				
	<i>Biological requirement</i>	<i>Expected value</i>	<i>Whole system</i>																	
1	Optimisation of filtration process (quality of permeate, sludge concentration, technical performance)																Evaluate quality of filtration with regular analysis on reactor content and permeate; evaluate technical performance of filtration process with measuring the flow through speed			
2	Optimisation of VFA production	min 3 g/L* in reactor															Measure regularly VFA concentration in reactor/permeate			
3	Optimisation of NH4+ production	min 0.27 g/L* in reactor															Measure regularly NH4+ concentration in reactor/permeate			
4	Optimisation of CO2 production																Measure regularly CO2 production			
5	Optimisation of OM degradation efficiency**	min 20%															Evaluate regularly OM efficiency of the prototype based on regular analysis			

CONFIDENTIAL REPORT

6	Optimisation of Nitrogen degradation efficiency	min 35%	Evaluate regularly N efficiency of the prototype based on regular analysis
7	Optimisation of Fibres degradation efficiency***	min 15%	Evaluate regularly Fibres efficiency of the prototype based on regular analysis

*Expected process values are determined based on experimental data gained on Melissa lab reactors at EPAS and on model-based estimation as described in TN71.1.

**OM degradation efficiency evaluation: see section Optimization of OM degradation efficiency.

***Fibre degradation efficiency evaluation: see section Optimization of Fibres degradation efficiency.

Draft Report

3. Tests nomenclature and procedures

3.1 Nomenclature

The aim of the functional tests is to evaluate the prototype reactor in order to improve the system and prevent instance of identical problems on the pilot reactor. Based on the requirements listed above, the necessary tests must be established and classified.

The nomenclature used for the tests is described below in Figure 4.




Figure 4. Test plan nomenclature

Therefore, for instance the test with number O.a.7.F.1 will concern a test in operation phase performed to check the possibility of clogging of an element from the filtration unit. The tests classification by number is presented in section 5.2. Test plan: classification by number.

3.2 Tests procedures

All tests results will be reported under table format and presented in MELISSA TN71.9.3.

The global procedures to be followed to perform the tests are described below. Some procedures are applicable for testing several instruments.

3.2.1 Hardware phase

- Homogeneous mixing

1. Check visually once a day that the stirrer is turning and the absence of dead zones.

CONFIDENTIAL REPORT

2. During 10 consecutive days, take samples from bottom and top of liquid.
 3. Analyze DM, ashes, NH₄⁺, pH, EC, CODs, VFA.
 4. Check statistically the absence of significant difference between the two samples groups.
 5. If samples are homogeneous, mixing is accepted as homogeneous.
- Stable heating
 1. Read once a day temperature inside the reactor measured continuously by the probe TS-R-001 on PC interface.
 2. Temperature shall not exceed the range 53°C-57°C.
 - Gas tightness
 - Test of the entire system (reactor + gas loop)
 1. Fill high-pressure part of the loop with compressed air until a pressure of around 3 bars.
 2. Monitor pressure in buffer tank R-G-001 over 1 hour.
 3. Measure pressure in Gas loop with pressure sensors PD-G-001 and PD-G-002 and check pressure stability.
 - Test of small leaks
 1. Fill the part of the loop concerned by the test with compressed air (250mbar in low pressure part, 2500mbar in high pressure part).
 2. Spray water based solution with high surface tension on the tested part.
 3. Check absence of leaks.
 4. A leak is detected when air bubbling appears.
 - Liquid tightness
 1. Fill tanks with water (R-001, R-F-001).
 2. Check visually, instrument by instrument, the absence of liquid leakage.
 3. Re-check after 24 hours.
 - Running of sensors and actuators
 1. Fill tank R-001 with water.
 2. Open and close all manual valves to check their operability
 3. Switch on all electrical instruments and check visually one by one their operation.

3.2.2 Operation phase

3.2.2.1 Hardware evaluation

- Absence of clogging

1. Check visually once a day existence of liquid stream through membrane, pumps, valves and connections.

- Absence of corrosion/ fouling

1. Check visually and regularly the absence of corrosion or fouling on instruments.
2. Sensors shall be tested during the calibration (to avoid too much openings of the system).
3. Other elements can be checked once a week.
4. Measure nickel and iron concentrations in the prototype.
5. Filtration unit: check evolution of fouling and absence of clogging with follow up of the permeate flow through the membrane speed.
6. The flow through speed shall approximate $6L.m^{-2}.h^{-1}$ (Stephenson *et al*, 2000).
7. Based on its diminution, evaluate the necessary frequency for membrane cleaning and replacing.

- Accuracy and repeatability of measurements: calibration

1. Calibration shall be operated at a certain frequency, specific of the instrument and fixed by the constructor or by experimental determination.

2. Put the tested sensor off-line.

- Calibration with standards:

3. Evaluate the degree of conformity of the output of the tested measuring instrument to the ideal value of the measured variable by some type of standard. Degree of conformity is given by the deviation from the ideal value. Acceptable deviation is fixed by the constructor.

- Calibration without standards

3. Evaluate the degree of conformity of the output of the tested measuring instrument to the value of any medium measured by a calibrated Iso-certificated measuring instrument.

- Absence of instrument deterioration

1. Check visually and regularly the absence of physical deterioration of instruments.
2. Sensors shall be tested during the calibration.
3. Other elements can be checked once a week.

CONFIDENTIAL REPORT

- Absence of reactor deterioration

1. Check visually once a week absence of physical deterioration of reactors.

- Desired answer to user or controller action

For each concerned instrument:

1. Execute user or controller action

2. Check adequacy of answer

- Regulation of permeate production

1. Estimate every day the flow of permeate produced (L/d) based on the volume measurement

2. Compare it to the set point of the program

3. Experimental flow should be included in the range $[0.1 \times set; 0.9 \times set]$.

- Regulation of gas loop

1. Record pressure in the reactor on-line:

- a. Measurements every minute during a few hours to check quickness of the gas loop answer

- b. Measurements every day during 10 days to check stability of the regulation in the time

2. Estimate stability of pressure.

- Configuration of reactor

1. Evaluate during all operation time general configuration of the reactor by reporting all problems and troubleshooting

- Configuration of filtration unit

1. Evaluate during all operation time general configuration of the filtration unit by reporting all problems and troubleshooting

- Configuration of gas loop

1. Evaluate during all operation time general configuration of the gas loop by reporting all problems and troubleshooting

3.2.2.2 Process evaluation

These tests are based on regular analysis performed on the influent, the filtrate and the reactor content as described in Table 4.

Table 4. Analysis frequency

	Frequency (per week)		
	Influent	Reactor content	Filtrate
DM	1	3	3
Ashes	1	3	3
pH	1	3	3
EC	1	3	3
VFA	1	1	3
NH ₄ ⁺ -N	1	1	3
N total	1	1	3
COD total	1	1	1
COD soluble	1	1	1
Gas	5		
H ₂ S	1		

Once on-line analyzers are installed, the frequency of the concerned parameters can be increased.

- Optimization of filtration process

- Quality of filtrate

1. Take three samples of permeate per week.
 2. Measure VFA, COD total and soluble, Total nitrogen, ammonium, dry matter and ashes.
 3. Evaluate filtrate quality by comparing:
 - a. VFA and ammonium in permeate and in reactor content: no loss of VFA and ammonium should be detected after the filtration step since these products are further used in the MELISSA loop
 - b. COD total and soluble of permeate: they should be similar since the ultrafiltration retains the particles
 - c. Total nitrogen and ammonium of permeate should be in the same range since only soluble nitrogen should be present in the filtrate (soluble nitrogen being essentially ammonium)
 - d. Dry matter and ashes of permeate: they can be compared to dry matter and ashes of the reactor content. The dry matter should be constant in the time and lower than the one of the reactor content, which should increase in the time.
- Concentration of reactor content

CONFIDENTIAL REPORT

1. Take three samples from the reactor content per week.
2. Measure dry matter, ashes, COD total and soluble.
3. Evaluate increase of these parameters with time due to filtration and determine frequency required for drain
 - Filtration process technical performance (see also section 3.2.2.1 : clogging and fouling of membrane)
1. Measure the flow through speed once a week.
2. The flow through speed shall approximate $6\text{L}\cdot\text{m}^{-2}\cdot\text{h}^{-1}$ (Stephenson *et al*, 2000).
- Optimization of VFA production
 1. Take three samples from the permeate produced per week.
 2. Measure VFA concentration by GC analysis.
 3. VFA concentration shall be upper than 3000mg/L.
 4. Investigate the factors of variation of VFA production
- Optimization of NH_4^+ production
 - In absence of on-line ammonium analyzer
 1. Take three samples from the permeate produced per week.
 2. Measure ammonium with Dr Lange kits.
 - In presence of on-line ammonium analyzer
 3. Record on-line ammonium measurements.
 4. Ammonium concentration shall be upper than 270mg/L.
 5. Investigate the factors of variation of ammonium production
- Optimization of CO_2 production
 1. Measure every day the volume of gas produced
 2. Analyze every day the composition of the gas phase
 3. Evaluate the CO_2 production rate
 4. Investigate the factors of variation of CO_2 production
- Optimization of OM degradation efficiency
 1. Based on regular analysis, evaluate the OM degradation efficiency

CONFIDENTIAL REPORT

The OM degradation efficiency can only be approximated since the sludge is a complex mix of products and its composition can hardly be precisely determined. Two different methods of evaluation are used to approach the effective efficiency in a simplified model:

- Using the known concentrations of the degradation products:

$$\eta_{OM1} = \frac{OM_{biod}}{OM_{inf}} = \frac{(VFA_{eff} - VFA_{inf}) + CO_2 + CH_4}{OM_{inf}}$$

Where:

- η_{OM1} = OM biological degradation efficiency
- OM_{biod} = cumulative biodegraded OM mass (mg)
- OM_{inf} = cumulative OM mass in influent (mg)
- $VFA_{inf/eff}$ = cumulative VFA mass in influent/effluent (mg)
- CO_2 = cumulative mass of CO2 produced (mg)
- CH_4 = cumulative mass of CH4 produced (mg)

This formula does not take into account the other possible degradation products such as lactate, ethanol... It is thus an under-estimation of the effective efficiency.

- Using the global balance on organic matter:

$$\eta_{OM2} = \frac{OM_{inf} - OM_{eff} - Accu}{OM_{inf}}$$

Where:

- η_{OM2} = OM biological degradation and mechanical removal efficiency
- OM_{eff} = cumulative mass of organic matter in effluent (mg)
- $Accu$ = accumulation (positive or negative) of organic matter in the reactor (mg)

This formula gives a simplified model closer from the reality.

2. OM degradation efficiency should be upper than 20%
 3. Investigate the factors of variation of the OM efficiency
- Optimization of Nitrogen degradation efficiency
 1. Based on regular analysis, evaluate the Nitrogen degradation efficiency

As for the organic matter efficiency, the nitrogen efficiency can only be estimated. Two estimators are used for its evaluation:

- Using the known concentrations of the degradation product:

$$\eta_{N1} = \frac{Norg_{biod}}{Norg_{inf}} = \frac{NH4_{eff} - NH4_{inf}}{Norg_{inf}}$$

Where:

- η_{N1} = nitrogen biodegradation efficiency
- $Norg_{biod}$ = cumulative biodegraded organic nitrogen mass (mg)
- $Norg_{inf}$ = cumulative organic nitrogen mass in influent (mg)
- $NH4_{inf}$ = cumulative ammonium mass in influent (mg)
- $NH4_{eff}$ = cumulative ammonium mass in effluent (mg)

- Using the global balance on nitrogen:

$$\eta_{N2} = \frac{Norg_{inf} - Norg_{eff}}{Norg_{inf}}$$

Where:

- η_{N2} = nitrogen biodegradation and mechanical removal efficiency
- $Norg_{eff}$ = cumulative organic nitrogen mass in effluent (mg)

2. Nitrogen degradation efficiency should be upper than 35%
3. Investigate the factors of variation of Nitrogen efficiency

▪ Optimization of Fibres degradation efficiency

1. Based on regular analysis, evaluate the fibres degradation efficiency

The fibre degradation efficiency is approached with the assumption that the non-proteic organic matter corresponds mainly to fibres.

$$\eta_{fibres} = \frac{Fibres_{deg}}{Fibres_{inf}}$$

$$Fibres_{inf} = OM_{inf} - prot_{inf}$$

$$Fibres_{deg} = OM_{biod} - prot_{biod} = OM_{inf} \cdot \eta_{OM1} - prot_{inf} \cdot \eta_{N1}$$

Where:

- η_{fibres} = fibres biodegradation efficiency
- $Fibres_{deg}$ = cumulative degraded fibres mass (mg)
- $Fibres_{inf}$ = cumulative fibres mass in influent (mg)

CONFIDENTIAL REPORT

- $prot_{biode}$ = cumulative biodegraded proteins mass (mg)

Proteins are determined theoretically by multiplying the amount of organic nitrogen by 6.25, which is a ratio determined based on analysis of nitrogen composition of amino-acids and classically used in protein determination (Jones, 1931).

2. Fibres degradation efficiency should be upper than 15%
3. Investigate the factors of variation of Fibres efficiency.

Draft Report

4. Conclusions

The functional test plan gives a structure of work to evaluate the hardware of the prototype waste compartment and the process. Based on the requirements of the reactor, an analysis of the important hardware and process requirements was performed. The test plan was established based on this analysis.

Tests on the hardware phase are performed during construction of the reactor, assembly of the prototype waste compartment and start-up.

Tests on the operation phase concern an evaluation of the prototype running on a representative period. Period for functional tests is usually defined based on the cycles of the process. To evaluate the prototype reactor, tests will be realized on a period of one month corresponding to three HRT (Hydraulic Residence Time).

Finally, evaluation of the tests results will generate an objective criticism of the prototype reactor, and thus knowledge to be transferred to the construction of the pilot reactor

5. References

Jones, D.B.: Factors for Converting Percentages of Nitrogen in Foods and Feeds into Percentages of Protein. United States Department of Agriculture, Circular No. 183. Slightly revised edition 1941 (Original version 1931).

Stephenson, T., Judd, S., Jefferson, B. and Brindle, K. (2000). Membrane bioreactors for wastewatertreatment. IWA Publishing

6. ADDENDUM

6.1 Test plan: classification by instrument

The requirements and associated test plan related to the hardware phase can be divided in 3 different groups: the hardware related to the reactor, to the filtration unit, and to the gas loop. The following tables present the requirements related to all the instrumentation.

Instruments		Requirements																		
Reference	Description	HARDWARE PHASE				OPERATION PHASE														
		Homogeneous mixing	Stable heating of the reactor	Gas / liquid tightness	Running of sensors and actuators	Hardware evaluation									Process evaluation					
Absence of clogging	Absence of corrosion / foaming					Accuracy and repeatability of measurements	Absence of instrument deterioration	Absence of reactor deterioration	Desired answer to user or controller action	Regulation of permeate production	Regulation of gas loop	Configuration of reactor	Configuration of filtration unit	Configuration of gas loop	Optimisation of filtration process	Optimisation of VFA production	Optimisation of NH4+ production	Optimisation of CO2 production?	Optimisation of OM degradation efficiency	Optimisation of Nitrogen degradation efficiency
REACTOR																				
R-001	Reactor																			
BL-R-001	Mixer for the bioreactor, equipped with LC-impeller																			
HX-R-001	Heat exchanger																			

CONFIDENTIAL REPORT

PMP-R-001	Influent pump																					
PD-R-001	Precision stainless steel pressure transmitter bioreactor																					
PD-R-002	Precision stainless steel pressure transmitter bioreactor																					
TS-R-001	Temperature sensor																					
TT-R-001	Temperature transmitter																					
pHS-R-001	pH sensor																					
pHT-R-001	pH transmitter																					
	Valves, connections																					
FILTRATION UNIT																						
R-F-001	Buffer tank																					
R-F-002	Permeate tank																					
M-F-001	Membrane																					
WD-F-001	Balance																					
PMP-F-001	Pump																					
PD-F-001	Pressure transducer before filtration module																					
PD-F-002	Pressure transducer after filtration module																					
PD-F-003	Pressure transducer on permeate flow																					
TS-F-001	Temperature sensor																					
TT-F-001	Temperature transmitter																					
FD-F-001	Flow meter																					
LD-F-001	Level sensor in buffer tank																					
SS-F-001	Turbidity sensor																					
ST-F-001	Turbidity transmitter																					
NS-F-001	Ammonium analyser																					
V-F-001	Software controlled valve between reactor and buffer tank																					
V-F-006	Software controlled valve between filtration module and buffer tank																					
V-F-011	Software controlled valve for permeate flow back to buffer tank																					
V-F-013	Software controlled valve for effluent flow																					
V-F-002	Manual controlled valve between buffer tank and pump																					

CONFIDENTIAL REPORT

V-F-003	Manual controlled valve between buffer tank and filtration module																			
V-F-004	Manual controlled valve before membrane module																			
V-F-005	Manual controlled valve after membrane module																			
V-F-007	Manual controlled valve between reactor and buffer tank																			
V-F-008	Manual controlled valve between reactor and buffer tank																			
V-F-009	Manual controlled valve between reactor and buffer tank																			
V-F-012	Manual controlled valve before permeate tank																			
V-F-014	Manual controlled valve between reactor and buffer tank																			
V-F-015	Manual controlled valve between reactor and buffer tank																			
	Connections																			
GAS LOOP																				
R-G-001	Pressure vessel: buffer for produced gas at 4 bar																			
HX-G-001	Cooler																			
PMP-G-001	Master pump that generates air flow through gas loop																			
PD-G-001	Precision stainless steel pressure transmitter bioreactor																			
PD-G-002	Precision stainless steel pressure transmitter pressure vessel																			
GS-G-001	Gas analyser																			
GS-G-002	Gas analyser																			
PI-G-001	Pressure on suction side of PMP-G-001																			
PI-G-002	Pressure at outlet gas analyser 1																			
PI-G-003	Pressure at outlet gas analyser 2																			
PI-G-004	Controlled backpressure by PR-G-004																			
PI-G-005	Controlled pressure by PR-G-001																			

CONFIDENTIAL REPORT

PI-G-006	Inlet pressure to PR-G-001																	
FI-G-001	Rotameter for flow through gas loop and analysers																	
PR-G-001	spring loaded, diaphragm-sensed backpressure regulator: regulates pressure in buffer vessel R-G-001, relieves net gas produced																	
PR-G-004	Self-contained spring loaded pressure reducing regulator with negative bias, regulates bioreactor pressure																	
V-G-001	Valve regulating the flow through gas loop and gas analysers																	
V-G-002	Valve regulating the flow through gas loop and gas analyser 1																	
V-G-003	Valve regulating the flow through gas loop and gas analyser 2																	
V-G-004	Safety pressure relief valve on pressure vessel R-G-001																	
V-G-005	Valve regulating the flow through gas loop																	
V-G-006	Valve regulating the addition of N ₂ -gas at reactor start-up																	
V-G-007	Automatic liquid drain on vessel R-G-001																	
	Connections																	

6.2 Test plan: classification by number

Table 5. Tests classification

Test nb	Phase	Sub-Phase	Requirement nb	Tested requirement	Sub-system	Test sub-number	Instrument ref	Instrument description	
H.1.R.1	H.		1.	Homogeneous mixing	R.	1	BL-R-001	Mixer	
							PLC	Control	
H.2.R.1			2.	Stable heating of the reactor (55°C)	R.	1	HX-R-001	Heat exchanger	
								PLC	Control
								HX-G-001	Cooler
H.3.R.1			3.	Gas tightness	R.	1	R-001	Reactor	
								BL-R-001	Mixer for the bioreactor, equipped with LC-impeller
								HX-R-001	Heat exchanger
								PD-R-001	stainless steel pressure transmitter bioreactor
								PD-R-002	Precision stainless steel pressure transmitter bioreactor
								TS-R-001	Temperature sensor
								pHS-R-001	pH sensor
								pHT-R-001	pH transmitter
		Valves, connections							
H.3.F.1					F.	1	R-F-001	Buffer tank	
H.3.G.1					G.	1	R-G-001	Pressure vessel: buffer for produced gas at 4 bar	
								HX-G-001	Cooler
								PMP-G-001	Master pump that generates air flow through gas loop
								PD-G-001	Precision stainless steel pressure transmitter bioreactor
								PD-G-002	Precision stainless steel pressure transmitter pressure vessel
								GS-G-001	Gas analyser
								GS-G-002	Gas analyser
								PI-G-001	Pressure on suction side of PMP-G-001
								PI-G-002	Pressure at outlet gas analyser 1
								PI-G-003	Pressure at outlet gas analyser 2
								PI-G-004	Controlled backpressure by PR-G-004
	PI-G-005	Controlled pressure by PR-G-001							
	PI-G-006	Inlet pressure to PR-G-001							

Draft Report

						FI-G-001	Rotameter for flow through gas loop and analysers
						PR-G-001	spring loaded, diaphragm-sensed backpressure regulator: regulates pressure in buffer vessel R-G-001, relieves net gas produced
						PR-G-004	Self-contained spring loaded pressure reducing regulator with negative bias, regulates bioreactor pressure
						V-G-001	Valve regulating the flow through gas loop and gas analysers
						V-G-002	Valve regulating the flow through gas loop and gas analyser 1
						V-G-003	Valve regulating the flow through gas loop and gas analyser 2
						V-G-004	Safety pressure relief valve on pressure vessel R-G-001
						V-G-005	Valve regulating the flow through gas loop
						V-G-006	Valve regulating the addition of N ₂ -gas at reactor start-up
						V-G-007	Automatic liquid drain on vessel R-G-001
							Connections
H.4.R.1		4.	Liquid tightness	R.	1	R-001	Reactor
						BL-R-001	Mixer for the bioreactor, equipped with LC-impeller
						HX-R-001	Heat exchanger
						PMP-R-001	Influent pump
						PD-R-001	Precision stainless steel pressure transmitter bioreactor
						PD-R-002	Precision stainless steel pressure transmitter bioreactor
						TS-R-001	Temperature sensor
						pHS-R-001	pH sensor
							Valves, connections
H.4.F.1				F.	1	R-F-001	Buffer tank
						R-F-002	Permeate tank
						PMP-F-001	Pump
						PD-F-001	Pressure transducer before filtration module
						PD-F-002	Pressure transducer after filtration module

Draft Report

						PD-F-003	Pressure transducer on permeate flow
						TS-F-001	Temperature sensor
						FD-F-001	Flow meter
						LD-F-001	Level sensor in buffer tank
						SS-F-001	Turbidity sensor
						NS-F-001	Ammonium analyser
						V-F-001	Software controlled valve between reactor and buffer tank
						V-F-006	Software controlled valve between filtration module and buffer tank
						V-F-011	Software controlled valve for permeate flow back to buffer tank
						V-F-013	Software controlled valve for effluent flow
						V-F-002	Manual controlled valve between buffer tank and pump
						V-F-003	Manual controlled valve between buffer tank and filtration module
						V-F-004	Manual controlled valve before membrane module
						V-F-005	Manual controlled valve after membrane module
						V-F-007	Manual controlled valve between reactor and buffer tank
						V-F-008	Manual controlled valve between reactor and buffer tank
						V-F-009	Manual controlled valve between reactor and buffer tank
						V-F-012	Manual controlled valve before permeate tank
						V-F-014	Manual controlled valve between reactor and buffer tank
						V-F-015	Manual controlled valve between reactor and buffer tank
							Connections
H.4.G.1				G.	1	V-G-007	Automatic liquid drain on vessel R-G-001
							Connections
H.5.R.1		5.	Running of sensors and actuators	R.	1	PMP-R-001	Influent pump
						PD-R-001	Precision stainless steel pressure transmitter bioreactor
						PD-R-002	Precision stainless steel pressure transmitter bioreactor

H.5.F.1	F.	1	TS-R-001	Temperature sensor
			pHS-R-001	pH sensor
			pHT-R-001	pH transmitter
			PLC	Control system
				Valves, connections
			WD-F-001	Balance
			PMP-F-001	Pump
			PD-F-001	Pressure transducer before filtration module
			PD-F-002	Pressure transducer after filtration module
			PD-F-003	Pressure transducer on permeate flow
			TS-F-001	Temperature sensor
			TT-F-001	Temperature transmitter
			FD-F-001	Flow meter
			LD-F-001	Level sensor in buffer tank
			SS-F-001	Turbidity sensor
			ST-F-001	Turbidity transmitter
			NS-F-001	Ammonium analyser
			V-F-001	Software controlled valve between reactor and buffer tank
			V-F-006	Software controlled valve between filtration module and buffer tank
			V-F-011	Software controlled valve for permeate flow back to buffer tank
			V-F-013	Software controlled valve for effluent flow
			V-F-002	Manual controlled valve between buffer tank and pump
			V-F-003	Manual controlled valve between buffer tank and filtration module
V-F-004	Manual controlled valve before membrane module			
V-F-005	Manual controlled valve after membrane module			
V-F-007	Manual controlled valve between reactor and buffer tank			
V-F-008	Manual controlled valve between reactor and buffer tank			
V-F-009	Manual controlled valve between reactor and buffer tank			
V-F-012	Manual controlled valve before permeate tank			

Draft Report

						V-F-014	Manual controlled valve between reactor and buffer tank						
						V-F-015	Manual controlled valve between reactor and buffer tank						
O.a.1.F.1	O.	a.	1.	Absence of clogging	R.	1	PMP-R-001	Influent pump					
												Valves, connections	
											M-F-001	Membrane	
											PMP-F-001	Pump	
											V-F-001	Software controlled valve between reactor and buffer tank	
											V-F-006	Software controlled valve between filtration module and buffer tank	
											V-F-011	Software controlled valve for permeate flow back to buffer tank	
											V-F-013	Software controlled valve for effluent flow	
											V-F-002	Manual controlled valve between buffer tank and pump	
											V-F-003	Manual controlled valve between buffer tank and filtration module	
										F.	1	V-F-004	Manual controlled valve before membrane module
												V-F-005	Manual controlled valve after membrane module
												V-F-007	Manual controlled valve between reactor and buffer tank
												V-F-008	Manual controlled valve between reactor and buffer tank
												V-F-009	Manual controlled valve between reactor and buffer tank
							V-F-012	Manual controlled valve before permeate tank					
							V-F-014	Manual controlled valve between reactor and buffer tank					
							V-F-015	Manual controlled valve between reactor and buffer tank					
								Connections					
O.a.2.R.1	O.	a.	2.	Absence of corrosion / fouling	R.	1	R-001	Reactor					
								BL-R-001	Mixer for the bioreactor, equipped with LC-impeller				
								HX-R-001	Heat exchanger				
								PD-R-001	Precision stainless steel pressure transmitter bioreactor				

Draft Report

						PD-R-002	Precision stainless steel pressure transmitter bioreactor
						TS-R-001	Temperature sensor
						pHS-R-001	pH sensor
							Valves, connections
O.a.2.F.1				F.	1	R-F-001	Buffer tank
						R-F-002	Permeate tank
						PMP-F-001	Pump
						PD-F-001	Pressure transducer before filtration module
						PD-F-002	Pressure transducer after filtration module
						PD-F-003	Pressure transducer on permeate flow
						TS-F-001	Temperature sensor
						FD-F-001	Flow meter
						LD-F-001	Level sensor in buffer tank
						SS-F-001	Turbidity sensor
						NS-F-001	Ammonium analyser
						V-F-001	Software controlled valve between reactor and buffer tank
						V-F-006	Software controlled valve between filtration module and buffer tank
						V-F-011	Software controlled valve for permeate flow back to buffer tank
						V-F-013	Software controlled valve for effluent flow
						V-F-002	Manual controlled valve between buffer tank and pump
						V-F-003	Manual controlled valve between buffer tank and filtration module
						V-F-004	Manual controlled valve before membrane module
						V-F-005	Manual controlled valve after membrane module
						V-F-007	Manual controlled valve between reactor and buffer tank
						V-F-008	Manual controlled valve between reactor and buffer tank
						V-F-009	Manual controlled valve between reactor and buffer tank
						V-F-012	Manual controlled valve before permeate tank

Draft Report

O.a.2.G.1	G.	1	V-F-014	Manual controlled valve between reactor and buffer tank
			V-F-015	Manual controlled valve between reactor and buffer tank
				Connections
			M-F-001	Membrane
			R-G-001	Pressure vessel: buffer for produced gas at 4 bar
			HX-G-001	Cooler
			PMP-G-001	Master pump that generates air flow through gas loop
			PD-G-001	Precision stainless steel pressure transmitter bioreactor
			PD-G-002	Precision stainless steel pressure transmitter pressure vessel
			GS-G-001	Gas analyser
			GS-G-002	Gas analyser
			PI-G-001	Pressure on suction side of PMP-G-001
			PI-G-002	Pressure at outlet gas analyser 1
			PI-G-003	Pressure at outlet gas analyser 2
			PI-G-004	Controlled backpressure by PR-G-004
			PI-G-005	Controlled pressure by PR-G-001
			PI-G-006	Inlet pressure to PR-G-001
			FI-G-001	Rotameter for flow through gas loop and analysers
			PR-G-001	spring loaded, diaphragm-sensed backpressure regulator: regulates pressure in buffer vessel R-G-001, relieves net gas produced
			PR-G-004	Self-contained spring loaded pressure reducing regulator with negative bias, regulates bioreactor pressure
V-G-001	Valve regulating the flow through gas loop and gas analysers			
V-G-002	Valve regulating the flow through gas loop and gas analyser 1			
V-G-003	Valve regulating the flow through gas loop and gas analyser 2			
V-G-004	Safety pressure relief valve on pressure vessel R-G-001			

Draft Report

						V-G-005	Valve regulating the flow through gas loop
						V-G-006	Valve regulating the addition of N ₂ -gas at reactor start-up
						V-G-007	Automatic liquid drain on vessel R-G-001
							Connections
O.a.3.R.1		3.	Accuracy and repeatability of measurements	R.	1	PD-R-001	Precision stainless steel pressure transmitter bioreactor
O.a.3.R.2			2		PD-R-002	Precision stainless steel pressure transmitter bioreactor	
O.a.3.R.3					3	TS-R-001	Temperature sensor
O.a.3.R.4					4	TT-R-001	Temperature transmitter
O.a.3.F.1				F.	1	pHS-R-001	pH sensor
O.a.3.F.2					2	pHT-R-001	pH transmitter
O.a.3.F.3					1	WD-F-001	Balance
O.a.3.F.4					2	PD-F-001	Pressure transducer before filtration module
O.a.3.F.5					3	PD-F-002	Pressure transducer after filtration module
O.a.3.F.6					4	PD-F-003	Pressure transducer on permeate flow
O.a.3.F.7					5	TS-F-001	Temperature sensor
O.a.3.F.8					6	TT-F-001	Temperature transmitter
O.a.3.F.9					7	FD-F-001	Flow meter
O.a.3.G.1				G.	8	LD-F-001	Level sensor in buffer tank
O.a.3.G.2					9	SS-F-001	Turbidity sensor
O.a.3.G.3						ST-F-001	Turbidity transmitter
O.a.3.G.4					1	NS-F-001	Ammonium analyser
O.a.3.G.5					1	PD-G-001	Precision stainless steel pressure transmitter bioreactor
O.a.3.G.6					2	PD-G-002	Precision stainless steel pressure transmitter pressure vessel
O.a.3.G.7					3	GS-G-001	Gas analyser
O.a.3.G.8					4	GS-G-002	Gas analyser
O.a.3.G.9					5	PI-G-001	Pressure on suction side of PMP-G-001
				6	PI-G-002	Pressure at outlet gas analyser 1	
				7	PI-G-003	Pressure at outlet gas analyser 2	
				8	PI-G-004	Controlled backpressure by PR-G-004	
				9	PI-G-005	Controlled pressure by PR-G-001	

Draft Report

CONFIDENTIAL REPORT

O.a.3.G.10					10	PI-G-006	Inlet pressure to PR-G-001
O.a.3.G.11					11	FI-G-001	Rotameter for flow through gas loop and analysers
O.a.4.R.1	4.	Absence of instrument deterioration	R.	1	BL-R-001	Mixer for the bioreactor, equipped with LC-impeller	
					HX-R-001	Heat exchanger	
					PMP-R-001	Influent pump	
					PD-R-001	Precision stainless steel pressure transmitter bioreactor	
					PD-R-002	Precision stainless steel pressure transmitter bioreactor	
					TS-R-001	Temperature sensor	
					TT-R-001	Temperature transmitter	
					pHS-R-001	pH sensor	
					pHT-R-001	pH transmitter	
					PLC	Control system	
O.a.4.F.1			F.	1	M-F-001	Membrane	
					WD-F-001	Balance	
					PMP-F-001	Pump	
					PD-F-001	Pressure transducer before filtration module	
					PD-F-002	Pressure transducer after filtration module	
					PD-F-003	Pressure transducer on permeate flow	
					TS-F-001	Temperature sensor	
					TT-F-001	Temperature transmitter	
					FD-F-001	Flow meter	
					LD-F-001	Level sensor in buffer tank	
					SS-F-001	Turbidity sensor	
					ST-F-001	Turbidity transmitter	
					NS-F-001	Ammonium analyser	
					V-F-001	Software controlled valve between reactor and buffer tank	
					V-F-006	Software controlled valve between filtration module and buffer tank	
V-F-011	Software controlled valve for permeate flow back to buffer tank						
V-F-013	Software controlled valve for effluent flow						
V-F-002	Manual controlled valve between buffer tank and pump						

Draft Report

Draft Report

						V-F-003	Manual controlled valve between buffer tank and filtration module
						V-F-004	Manual controlled valve before membrane module
						V-F-005	Manual controlled valve after membrane module
						V-F-007	Manual controlled valve between reactor and buffer tank
						V-F-008	Manual controlled valve between reactor and buffer tank
						V-F-009	Manual controlled valve between reactor and buffer tank
						V-F-012	Manual controlled valve before permeate tank
						V-F-014	Manual controlled valve between reactor and buffer tank
						V-F-015	Manual controlled valve between reactor and buffer tank
							Connections
O.a.4.G.1				G.	1	R-G-001	Pressure vessel: buffer for produced gas at 4 bar
						HX-G-001	Cooler
						PMP-G-001	Master pump that generates air flow through gas loop
						PD-G-001	Precision stainless steel pressure transmitter bioreactor
						PD-G-002	Precision stainless steel pressure transmitter pressure vessel
						GS-G-001	Gas analyser
						GS-G-002	Gas analyser
						PI-G-001	Pressure on suction side of PMP-G-001
						PI-G-002	Pressure at outlet gas analyser 1
						PI-G-003	Pressure at outlet gas analyser 2
						PI-G-004	Controlled backpressure by PR-G-004
						PI-G-005	Controlled pressure by PR-G-001
						PI-G-006	Inlet pressure to PR-G-001
						FI-G-001	Rotameter for flow through gas loop and analysers

Draft Report

						PR-G-001	spring loaded, diaphragm-sensed backpressure regulator: regulates pressure in buffer vessel R-G-001, relieves net gas produced
						PR-G-004	Self-contained spring loaded pressure reducing regulator with negative bias, regulates bioreactor pressure
						V-G-001	Valve regulating the flow through gas loop and gas analysers
						V-G-002	Valve regulating the flow through gas loop and gas analyser 1
						V-G-003	Valve regulating the flow through gas loop and gas analyser 2
						V-G-004	Safety pressure relief valve on pressure vessel R-G-001
						V-G-005	Valve regulating the flow through gas loop
						V-G-006	Valve regulating the addition of N ₂ -gas at reactor start-up
						V-G-007	Automatic liquid drain on vessel R-G-001
							Connections
O.a.5.R.1		5.	Absence of reactor deterioration	R.	1	R-001	Reactor
O.a.5.F.1	F.			1	R-F-001	Buffer tank	
O.a.5.F.2				2	R-F-002	Permeate tank	
O.a.5.G.1				G.	1	R-G-001	Pressure vessel: buffer for produced gas at 4 bar
O.a.6.R.1		6.	Desired answer to user or controller action	R.	1	BL-R-001	Mixer for the bioreactor, equipped with LC-impeller
O.a.6.R.2	2				HX-R-001	Heat exchanger	
O.a.6.R.3	3				PMP-R-001	Influent pump	
O.a.6.R.4	4					Valves, connections	
O.a.6.F.1	F.			1	WD-F-001	Balance	
O.a.6.F.2				2	PMP-F-001	Pump	
O.a.6.F.3				3	SS-F-001	Turbidity sensor	
					ST-F-001	Turbidity transmitter	
O.a.6.F.4				4	NS-F-001	Ammonium analyser	
O.a.6.F.5				5	V-F-001	Software controlled valve between reactor and buffer tank	
O.a.6.F.6				6	V-F-006	Software controlled valve between filtration module and buffer tank	
O.a.6.F.7	7			V-F-011	Software controlled valve for permeate flow back to buffer tank		

CONFIDENTIAL REPORT

O.a.6.F.8					8	V-F-013	Software controlled valve for effluent flow
O.a.6.F.9					9	V-F-002	Manual controlled valve between buffer tank and pump
O.a.6.F.10					10	V-F-003	Manual controlled valve between buffer tank and filtration module
O.a.6.F.11					11	V-F-004	Manual controlled valve before membrane module
O.a.6.F.12					12	V-F-005	Manual controlled valve after membrane module
O.a.6.F.13					13	V-F-007	Manual controlled valve between reactor and buffer tank
O.a.6.F.14					14	V-F-008	Manual controlled valve between reactor and buffer tank
O.a.6.F.15					15	V-F-009	Manual controlled valve between reactor and buffer tank
O.a.6.F.16					16	V-F-012	Manual controlled valve before permeate tank
O.a.6.F.17					17	V-F-014	Manual controlled valve between reactor and buffer tank
O.a.6.F.18					18	V-F-015	Manual controlled valve between reactor and buffer tank
O.a.6.G.1				G.	1	HX-G-001	Cooler
O.a.6.G.2					2	PMP-G-001	Master pump that generates air flow through gas loop
O.a.6.G.3					3	PI-G-004	Controlled backpressure by PR-G-004
O.a.6.G.4					4	PI-G-005	Controlled pressure by PR-G-001
O.a.6.G.5					5	PR-G-001	spring loaded, diaphragm-sensed backpressure regulator: regulates pressure in buffer vessel R-G-001, relieves net gas produced
O.a.6.G.6					6	PR-G-004	Self-contained spring loaded pressure reducing regulator with negative bias, regulates bioreactor pressure
O.a.6.G.7					7	V-G-001	Valve regulating the flow through gas loop and gas analysers
O.a.6.G.8					8	V-G-002	Valve regulating the flow through gas loop and gas analyser 1
O.a.6.G.9					9	V-G-003	Valve regulating the flow through gas loop and gas analyser 2
O.a.6.G.10					10	V-G-004	Safety pressure relief valve on pressure vessel R-G-001

Draft Report

CONFIDENTIAL REPORT

O.a.6.G.11					11	V-G-005	Valve regulating the flow through gas loop
O.a.6.G.12					12	V-G-006	Valve regulating the addition of N ₂ -gas at reactor start-up
O.a.6.G.13					13	V-G-007	Automatic liquid drain on vessel R-G-001
O.a.7.1	7.	Regulation of permeate production	R. F.	1		PLC	Control system
						WD-F-001	Balance
						PMP-F-001	Pump
						PD-F-001	Pressure transducer before filtration module
						PD-F-002	Pressure transducer after filtration module
						PD-F-003	Pressure transducer on permeate flow
						FD-F-001	Flow meter
						LD-F-001	Level sensor in buffer tank
						SS-F-001	Turbidity sensor
						V-F-001	Software controlled valve between reactor and buffer tank
						V-F-006	Software controlled valve between filtration module and buffer tank
						V-F-011	Software controlled valve for permeate flow back to buffer tank
						V-F-013	Software controlled valve for effluent flow
O.a.8.1	8.	Regulation of gas loop	R. G.	1		PLC	Control system
						HX-G-001	Cooler
						PMP-G-001	Master pump that generates air flow through gas loop
						PD-G-001	Precision stainless steel pressure transmitter bioreactor
						PD-G-002	Precision stainless steel pressure transmitter pressure vessel
						PI-G-001	Pressure on suction side of PMP-G-001
						PI-G-002	Pressure at outlet gas analyser 1
						PI-G-003	Pressure at outlet gas analyser 2
						PI-G-004	Controlled backpressure by PR-G-004
						PI-G-005	Controlled pressure by PR-G-001
	PI-G-006	Inlet pressure to PR-G-001					

Draft Report

						FI-G-001	Rotameter for flow through gas loop and analysers
						PR-G-001	spring loaded, diaphragm-sensed backpressure regulator: regulates pressure in buffer vessel R-G-001, relieves net gas produced
						PR-G-004	Self-contained spring loaded pressure reducing regulator with negative bias, regulates bioreactor pressure
						V-G-001	Valve regulating the flow through gas loop and gas analysers
						V-G-002	Valve regulating the flow through gas loop and gas analyser 1
						V-G-003	Valve regulating the flow through gas loop and gas analyser 2
						V-G-004	Safety pressure relief valve on pressure vessel R-G-001
						V-G-005	Valve regulating the flow through gas loop
						V-G-006	Valve regulating the addition of N ₂ -gas at reactor start-up
						V-G-007	Automatic liquid drain on vessel R-G-001
O.a.9.R.1			9.	Configuration of reactor	R.	1	all instrumentation
O.a.9.F.1			10.	Configuration of filtration unit	F.	1	all instrumentation
O.a.9.G.1			11.	Configuration of gas loop	G.	1	all instrumentation
O.b.1.1	b.		1.	Optimisation of filtration process	F.	1	Whole system- Permeate stream
O.b.2.1			2.	Optimisation of VFA production		1	Whole system- Permeate stream
O.b.3.1			3.	Optimisation of NH ₄ ⁺ production		1	Whole system- Permeate stream
O.b.4.1			4.	Optimisation of CO ₂ production?		1	Whole system- Gas stream
O.b.5.1			5.	Optimisation of OM degradation efficiency		1	Whole system
O.b.6.1			6.	Optimisation of Nitrogen degradation efficiency		1	Whole system
O.b.7.1			7.	Optimisation of Fibres degradation efficiency		1	Whole system

Draft Report